



**INFRASTRUCTURE SERVICES DEPARTMENT**  
233 North Pecos La Trinidad, Suite 420  
San Antonio, Texas 78207

**(210) 335-6700 Office**  
**(210) 335-6713 Fax**

**COUNTY STANDARDS**  
**Traffic Control Devices (TCD)**  
**REQUIREMENTS FOR SUBDIVISIONS**

**EFFECTIVE 9-7-10**

**GROUND SIGN MOUNTING**

TxDOT Wedge Anchor Steel System with Thin Wall Tubing  
TxDOT SMD (TWT)-08 for signs under 15 SQ FT &  
SMD(SLIP-2) -08 for signs that meet area criteria and required supports.

**SIGN INSTALLATION, SIZE, LOCATION**

Compliant with FHWA MUTCD 2009 or TMUTCD 2006 rev which ever is more restrictive.

**REGULATORY SIGN RETROREFLECTIVE SHEETING**

TxDOT Type C-ASTM D4956-09<sup>ε1</sup> IV—High Intensity Prismatic

**WARNING SIGN RETROREFLECTIVE SHEETING**

TxDOT Type E-ASTM D 4956-09<sup>ε1</sup> XI—Diamond Grade-Fluorescent

**STREET NAME SIGNS**

Lettering will be composed of combination of lower-case with initial upper case letters.

Post Mounted – TxDOT Type C-ASTM D4956-09<sup>ε1</sup> IV—High Intensity Prismatic

Overhead – TxDOT Type D-ASTM D4956-09<sup>ε1</sup> XI—Diamond Grade—NonF

County Standard Detail is under revision.

**INSTALLATION**

Developer's Engineer meets specifications and requirements & submits TCD. as part of construction plans for review and approval.

Developer's contractor no longer pays County to furnish and install signs.

Developer's contractor furnishes and installs signs.

County inspects at final.

Henceforth if contractor has paid for signs, County will furnish those signs but will not install after 9-7-10.